

- e. Make, model, and type of all automatic fire detection devices.
 - f. Make, model, and type of audible/visual indicating appliances including decibel/candela rating.
 - g. Make, model, and type of fire department command center equipment.
 - h. Make, model, and type of all offsite reporting equipment.
 - i. Make, model, and type of wire or cable to be used for field wiring of the alarm system.
 - j. Make, model, and type of door hold open devices, smoke dampers, HVAC shutdown, commercial kitchen exhaust system devices affecting buildings or fire protection equipment.
6. Name, address, telephone number, and contact person at the offsite monitoring service.
 7. Name, address, telephone number, and contact person at the installing contractor.
 8. Name, address, telephone number, and contact person of the project.
 9. Names, addresses, telephone numbers, of emergency contact persons for the property.

OTHER INFORMATION REGARDING FIRE ALARMS

1. An Arkansas Licensed Fire Alarm Technician shall perform all work on fire alarms.
2. If the Fire Alarm Company is not doing the design build it is suggested that one set of plans be submitted for review prior to going out for bid. If this process is not followed the plans run the risk of being rejected for non-compliance.
3. Allow a one (1) week turnaround time for plan submittals.
4. Prior to acceptance test the Fire Alarm Company is required to pretest 100% of devices.
5. It is the responsibility of the Fire Alarm Company to schedule any other Fire Protection Contractors that may be needed to test out the system.
6. Acceptance test can only be scheduled by the Fire Alarm Company to assure that they are completely ready for the test.
7. Upon completion of the acceptance test the Fire Alarm Company shall submit the following.
 - a. Letter of Completion
 - b. A contract for inspection, testing and maintenance for a minimum of one year.
This contract doesn't have to be with the company that does the installations.
8. A copy of inspection reports shall be submitted to the Fire Marshal's Office.
9. Duct smokes shall have a remote annunciation when not visible from floor or 10' above floor.
10. Non-required systems shall meet the intent of the code.
11. No smokes shall be installed until all trades are done. Exception: UL listed covers can be placed over the smokes. ***(The plastic caps from the factory are not listed for the application)***
12. Any rebuttal to submittal or other requirements shall be made in writing to the Fire Marshal's Office with appropriate NFPA and/or Arkansas Fire Prevention Code documentation to support your position.
13. It is the alarm company's responsibility to research the codes from NFPA and the Arkansas Fire Prevention Code.
14. The Fire Marshal's Office does not design fire alarm systems we only verify that the systems are designed and installed per the intent of the code(s).